WETLAND CONSTRUCTION REQUIREMENTS

1. CONSTRUCTION LIMITS/CORRIDOR (INCLUDING ROADS AND STOCKPILE AREA) TO A MAXIMUM 40 FOOT WIDTH.
2. POST CONSTRUCTION GROUND CONTOURS AND ELEVATIONS MUST BE RESTORED TO THE ORIGINAL ELEVATIONS.
3. THE TOP 6" TO 12" OF THE TRENCH SHALL BE BACKFILLED WITH THE TOPSOIL AND/OR SOIL EXISTING PRIOR TO CONSTRUCTION.
4. EXCESS MATERIAL MUST BE REMOVED TO UPLAND AREAS AND DISPOSED OF OFF-SITE. TEMPORARY PLACEMENT/STOCKPILE FOR ABSOLUTE MINIMUM PERIOD OF TIME.
5. DISTURBED SLOPES AND STREAM BANKS MUST BE STABILIZED IMMEDIATELY UPON COMPLETION OF THE UTILITY LINE OR IMMEDIATELY AT EACH STREAM CROSSING.
6. NOTIFY COE DISTRICT ENGINEER AND RECEIVE WRITTEN APPROVAL PRIOR TO BEGINNING CONSTRUCTION.
7. INSTALL ANTI-SEEP COLLARS EVERY 150 FEET OR AS SHOWN ON PLANS.
8. NO FERTILIZER SHALL BE APPLIED WITHIN 10 FEET OF STREAM.
9. NO FRESH CONCRETE SHALL BE IN CONTACT WITH STREAMS.
10. SEEDING SHALL BE IN ACCORDANCE WITH THE SPECIFIED MIXTURE FOR WETLAND AREAS.

WETLAND CONSTRUCTION REQUIREMENTS			FAYETTEVILLE PUBLIC WORKS COMMISSION FAYETTEVILLE, N.C.	PWC	NO.	DATE	REVISION
SHEET NO. 1 OF 1	DWG. NO. N.6	DWG. BY: FAYPWC	WATER RESOURCES ENGINEERING DEPARTMENT				
	DATE: JULY 01, 2021	APPROVED BY: J.E.G.					

N6-WETLAND-NOTES.dwg